

Questions and Answers for ITB 13-05-01: Manufacturing and Installation of Wayfinding Signs
June 11, 2013

Q. What re the size of the Z Bars?

A. Z Bars are ½" Aluminum x per specification and powder coated per color of sign unit.

Q. Is the "Horseshoe Bracket" a standard U-Bolt or is a custom bracket required?

A. Custom bracket.

Q. Is the entire sign powder coated including the logo and removable directional panel?

A. The entire substrate is powder coated. The vinyl panel is applied on top.

Q. Is there a required timeframe for the install? Day or Night?

A. The timeframe specified to have the signs manufactured and installed is 45 days from the NTP. As for day or night, the only requirement is that no lane of traffic is blocked for installation.

Q. On Phase I drawing 2 types of locator signs are shown. On quantities, it says 2 each, is it 2 each of each type?

A. No, we changed the Relax...You're Here locator to a gateway sign at both ends of A1A/Ocean Drive. Therefore, there are 2 locator signs – Beach Access.

Q. For the 15 directional signs, can we provide one generic signed and sealed engineer drawing or will this require 15 separate sets?

A. We'll need one generic signed and sealed engineer drawing for each type of sign. With that drawing, we'll need separate pages with each location shown. Additionally, we want to see a full size mock up of the vinyl overlay to ensure the colors and type are correct.